

LAB 4 SSH CONFIGURATION

GURUCHANDHRAN M

TASK 1: ENABLING SSH IN ROUTER

ROUTER IP: 50.0.0.1

The screenshot displays a network simulation interface. On the left, a diagram shows a router connected to a PC. The router is labeled 'ROUTER' with IP '50.0.0.1' and the PC is labeled 'Win' with IP '50.0.0.10'. The connection is labeled 'SSH - TELNET'. On the right, a terminal window titled 'ROUTER' shows the following configuration commands and output:

```
ROUTER(config)#hostname R1
R1(config)#int eth0/0
R1(config-if)#ip address 50.0.0.1 255.0.0.0
R1(config-if)#no sh
R1(config-if)#exit
R1(config)#ip domain-name surennetwork.in
R1(config)#crypto key generate rsa 2048
% Invalid input detected at '^' marker.
R1(config)#crypto key generate rsa
The name for the keys will be: R1.surennetwork.in
Choose the size of the key modulus in the range of 360 to 4096 for your
General Purpose Keys. Choosing a key modulus greater than 512 may take
a few minutes.
How many bits in the modulus [512]: 2048
% Generating 2048 bit RSA keys, keys will be non-exportable...
[OK] (elapsed time was 7 seconds)
R1(config)#
*Jul 17 03:41:02.848: %SSH-5-ENABLED: SSH 1.99 has been enabled
R1(config)#username ccna privilege 15 secret ccna
R1(config)#ip ssh version 2
R1(config)#line vty 0 4
R1(config-line)#transport input ssh
R1(config-line)#login local
R1(config-line)#end
R1#
```

The terminal also shows the output of the 'show ip int br' command:

Interface	IP-Address	OK?	Method	Status	Prot
local					
Ethernet0/0	50.0.0.1	YES	manual	up	up
Ethernet0/1	unassigned	YES	TFTP	down	down
Ethernet0/2	unassigned	YES	TFTP	down	down

TASK 2: SSH VERIFICATION

PC IP: 50.0.0.10

The screenshot displays the same network simulation interface as Task 1. On the left, the diagram shows the router (50.0.0.1) and PC (50.0.0.10) connected via 'SSH - TELNET'. On the right, a terminal window titled 'QEMU (Win)' shows the PC's perspective. The user 'ccna' has logged in successfully. The terminal output shows the 'show ip int brief' command results, which match the router's configuration:

Interface	IP-Address	OK?	Method	Status	Prot
local					
Ethernet0/0	50.0.0.1	YES	manual	up	up
Ethernet0/1	unassigned	YES	TFTP	down	down
Ethernet0/2	unassigned	YES	TFTP	down	down
Ethernet0/3	unassigned	YES	TFTP	down	down